

INFORMATION SHEET

Complete Digital Solutions





27MBTS3P SPECIFICATIONS Temporary 3 Phase Site Power Box

- Made from 1.2mm Pre Galvanised Steel Sheet As1397 rated.
- Internal Insulating Panel AS1795/IEC60893.
- IP23 Rated.
- 500mm x 500mm Enclosure.
- 2 Piece compact kit for shipping to any job site conveniently. Stand assembles in less than 5 minutes complete.
- UV Stabilised Powder Coated 2-piece stand
- Cable restraint isolated tie rods on top and bottom fully installed.
 Additional metal brace/tie rod on bottom.
- 3 Phase Main Switch 100A.
- 5 pin 32 Amp 3 Phase socket to be mounted on outside of box.
- Separate 32 Amp Breaker for 3 Phase Socket.
- Separate 30 mA RCD for 3 Phase Socket
- 5x 10A Double Power Points with Active and Neutral switching.
- 1x 15A Power Point.
- Complete with lock for lockable lume box.
- Fully wired and tested in Australia by licenced electricians with locally sourced SAA approved electrical parts.

Please ring store for pricing



Assembled Dimensions (W x D x H) 520mm x 610mm x 1875mm

Kit Dimensions (W x D x H) Box 1 760mm x 525mm x 245mm **Box 2** 520mm x 65mm x 1755mm